

TMC SPECIFICATION

NO. S 1328

REV: 0

COMPILED: CHECKED: APPD: SHEET OF

TITLE:

2/4/74

LSP-6 TEST PROCEDURE

TMC SPECIFICATION

NO. S1328

REV: ①

COMPILED:

CHECKED:

APPD:

SHEET

1

OF

2

TITLE:

LSP-6 Test Procedure

A. TEST EQUIPMENT REQUIRED

1. Audio Generator

B. PRELIMINARY

1. Check panel for mechanical faults.
2. Check panel for wiring errors.

C. PROCEDURE

1. Connect audio generator output to terminals 1 and 2 of TB1 on panel.
2. Switch on audio generator.
3. Adjust generator to 400 cycles and turn output control until audio tone is heard on LS-1 speaker.
4. Connect audio generator output to terminals 3 and 4 of TB1 on panel.
5. An audio tone should be heard on LS-2 speaker.

TMC SPECIFICATION

NO. S 1328

REV: 0

COMPILED: CHECKED: APPD: SHEET 2 OF 2

TITLE: LSP-6 Test Procedure

THE TECHNICAL MATERIAL CORPORATION

MAMARONECK, N.Y.

LSP-6 TEST DATA SHEET

SERIAL NO. _____

MFG. NO. _____

Mechanical check _____ OK

Wiring check _____ OK

Audio test for LS-1 _____ OK

Audio test for LS-2 _____ OK

DATE _____

TESTER _____

