DATE 4/11/59 SH. 1 OF 8 COMPLED BY N. K.		TMC	SPECIFICATION	NO.	S- 10026
	TITLE:	PRODUCTION	TESTING OF MODEL TIS-2		JOB
APPROVED	∑t.				1 soe/

INSTRUCTIONS FOR THE

PRODUCTION TESTING

OF THE

MODEL TIS-2

DATE 4/11/59 SH. 2 OF 8 COMPILED BY		TMC	SPECIFICATION	NO.	S - 10026
N.K.	TITLE:	PRODUCT 10	N TESTING OF MODEL TIS-2		JOB
APPROVED	<u> </u>				100

The F/S and Tone Intelligence System, Model TIS-2, is a modified version of the Model TIS-1. The following instruction sheets of the Model TIS-1 can be used for production testing:

Model TST-2see TMC Specification No. S-321Model TTU-1see TMC Specification No. S-320Model TTF-2see TMC Specification No. S-328

A new test procedure for the Model TTU-2 has been compiled on the following pages.

DATE 4/11/59 SH. 3 OF 8 COMPILED BY N.K.		TMC	SPECIFICATION	NO.	S - 10026
	TITLE:	PRODUCTION	TESTING OF MODEL TTU-2		JOB
APPROVED	(INC

INSTRUCTIONS FOR THE

PRODUCTION TESTING

OF THE

MODEL TTU-2

#00H — 100

DATE 4/11/59 SH. 4 OF 8 COMPILED BY		TMC	SPECIFICATION N	O. S - 10026
N.K.	TITLE:	PRODUCTION	TESTING OF THE MODEL TTU-2	JOB
APPROVED M.	a.			iore

INDEX

		PAGE
1.	Test Equipment required	5
2.	Test Instructions	5
3.	General Instrument Layout	6
4.	Test Sequence and Procedure	7
	A. General and Visual Inspection	7
	B. Frequency Adjustment and Output Test	7 and 8


DATE 4/11/59 SH. 5 OF 8 COMPILED BY		TMC	SPECI	FICAT	ON	NO.	S - 100)26
N.K.	TITLE:	PRODUCTION	TESTING OF	THE MODEL	TTU-2	<u> </u>	JOB	
APPROVED M.	En .						12	ne

1. TEST EQUIPMENT REQUIRED


- 1. Power supply Model TST-2.
- 2. Counter Berkeley Model 5558 or equivalent.
- 3. AC VIVM Hewlett-Packard Model 410B or equivalent.

2. TEST INSTRUCTIONS

Proceed as outlined in paragraph 4, Test Sequence and Procedure.



3. GENERAL INSTRUMENT LAYOUT



DATE 4/11/59 SH. 7 OF 8 COMPILED BY N.K.		TMC	SPECIFICATION	NO.	S - 10026
	TITLE:	PRODUCTION	TESTING OF THE MODEL TTU-2		JOB ,
APPROVED M.	Ku.				The

4. TEST SEQUENCE AND PROCEDURE

A. GENERAL AND VISUAL INSPECTION

- 1. Inspect the unit for obvious mechanical and electrical errors.
- 2. Be sure that all screws are tight.

B. FREQUENCY ADJUSTMENT AND OUTPUT TEST

- 1. Plug F/S transmit unit, Model TTU-2 into the pow r supply, Model TST-2.
- 2. Turn the output control R135 fully clockwise for maximum output.
- 3. Set Cl08 to one-balf its value.
- 4. Connect a jumper from terminal 4 to 5 on ElOl.
- 5. Turn power on and allow a warm up time of approximately 30 minutes.
- 6. Connect counter to pin 7 of V102 and adjust C126 to a frequency of approximately 200.4 kc/s. If you cannot obtain the specified frequency set capacitor C126 at one-half its capacity and adjust C118 for the specified frequency.
- 7. Connect counter to junction of R110, R111 and R112. The frequency should be approximately 197.4 kc/s.
- 8. Connect counter to terminal 1 and 2 on E101 and adjust C108 to a mark frequency of 2975 c/s.
- 9. Disconnect jumper from terminal 5 on ElOl and adjust Rl19 to the specified frequency shift.
- 10. Connect jumper again to terminal 5 on ElOl. If the mark frequency is not 2975 c/s readjust ClO8.

DATE 4/11/59 SPECIFICATION NO. S - 10026 TMC COMPILED BY TITLE: JOB N.K. PRODUCTION TESTING OF THE MODEL TTU-2

APPROVED

1806

- 11. Repeat steps 9 and 10 until the correct frequency shift and mark frequency are obtained.
- 12. Measure the output voltage in mark condition with a VTVM. It must exceed 0.45 V.

The unit which has met the specifications above must be placed in its final form with cover plates etc. and prepared for shipment.