

DATE 6/8/56

SH. 1 OF 6

COMPILED BY

TMC SPECIFICATION NO. S-297

TITLE: PRODUCTION TESTING OF CAB/FRAME (TMC PART #A-958) JOB E271P

APPROVED

*A.J.J.*

COMPLETE INSTRUCTIONS

for the

PRODUCTION TESTING

of the

CABINET/FRAME, TMC PART NO. A-958

DATE 6/8/56  
SH. 2 OF 6  
COMPILED BY

TMC SPECIFICATION NO. S-297

TITLE: PRODUCTION TESTING OF CAB/FRAME (TMC PART #A-958) JOB E271P

APPROVED *[Signature]* A.S.J.

INDEX

- 1) Purpose and Description
- 2) Test Equipment Required
- 3) General Instrument Layout
- 4) Test Instructions
- 5) Test Sequence and Procedure
- 6) Sample Report Sheet

DATE 6/8/56  
SH. 3 OF 6  
COMPILED BY

# TMC SPECIFICATION NO. S-297

TITLE: PRODUCTION TESTING OF CAB/FRAME (TMC PART #A-958) JOB E271P

APPROVED

435  
Page Issued A


1) Purpose and Description:

(see Instruction Book)

2) Test Equipment Required:

- a. Cabinet/Frame, A-958  
Test Unit, 8-829
- b. Ohmmeter, Simpson, Model 260 or  
equivalent

3) General Instrument Layout:



DATE 6/8/56  
SH. 4 OF 6  
COMPILED BY

TMC SPECIFICATION NO. S-297

TITLE: PRODUCTION TESTING OF CAB/FRAME (TMC PART #A-958) JOB E271P

APPROVED

*W B* AJJ

4) Test Instructions:

- a. Proceed as outlined in Test Sequence and Procedure, paragraph #5 to follow.
- b. Fill in blanks on Report Sheet, rejecting those units which do not meet the specifications stated herein.
- c. Sign Report Sheet and submit it to your supervisor.

5) Test Sequence and Procedure:

A General Inspection:

- a. Inspect the unit for obvious Mechanical and Electrical errors and be sure that all screws are tight.
- b. Inspect the Interlock switches and be sure that they are mounted correctly. Refer to S-292 if readjustment is necessary.
- c. Inspect the High Voltage Transformer for proper placement of jumpers and cable connections.
- d. Be sure that all by-pass condensers are properly wired and all are present. Reference must be made to CK-330 or to CK-321.

B Continuity Test:

- a. Connect the Test Unit as shown in paragraph #3, General Instrument Layout.
- b. Turn on the Power
- c. Turn the switch S-1 slowly through all positions, observing the light L-1.

The pilot indicator should light in all positions. If on one or more positions the indicator does not light, take action as stated in the chart for the location of faulty connector.

DATE 6/8/56  
 SH. 5 OF 6  
 COMPILED BY

TMC SPECIFICATION NO. S-297

TITLE: PRODUCTION TESTING OF CAB/FRAME (TMC PART #A-958) JOB E271P

APPROVED *[Signature]* Page Issued A

NOTE: If pilot indicator does not light in positions 21 and 22 of S-1, depress the polarity switch S-2. If indicator still does not light, refer to the chart for the location of faulty connector.

C Blower, B-501:

a. Depress the blower switch S-3.

The blower must then run. If not, refer CK-321

POSSIBLE LOCATION OF FAULT

S1 POS.	PIN	PART	PIN	PART	S1 POS.	PIN	PART	PIN	PART
1	A	P501	1	E501	20	L	P502	C	P502
2	F	P501	2	----	21	K	P502	lor2	J501
3	L	P501	3	----	22	J	P502	lor2	J501
4	C	P501	4	----					
5	W	P502	5	----					
6	H	P502	6	----					
7	B	P502	7	----					
8	M	----	8	----					
9	C	----	9	----					
10	B	----	10	----	23	I	P502	6	T501
11	E	----	11	----					
12	P	----	12	----					
13	U	----	P	P501					
14	V	----	S	P501					
15	X	----	R	P501					
16	T	----	H	P501					
17	S	P502	N	P501					
18	D	P502	One or more interlocks improperly wired. Use Ohmmeter to determine such faults.						
19	A	P502	Gnd	J501					

Pin 1 or 2 is determined by the polarity switch S-2.

When all of the preceding tests have been successfully completed, the Unit must be placed in its final form, cover plates on, etc., and prepared for shipment. On copy of Report Sheet shall be enclosed with each Cabinet/Frame, A-958.

DATE 6/8/56  
SH. 6 OF 6  
COMPILED BY

TMC SPECIFICATION NO. S-297

TITLE: PRODUCTION TESTING OF CAB/FRAME (TMC PART #A-958) JOB E271P

APPROVED W. J. ATT

SAMPLE

REPORT SHEET

CABINET/FRAME, A-958

	<u>ACCEPT</u>	<u>REJECT</u>
TEST A: General Inspection	-----	-----
TEST B: Continuity Test	-----	-----
TEST C: Blower, B-501	-----	-----

Serial Number \_\_\_\_\_

Accepted -----

Date \_\_\_\_\_

Rejected -----

Tested By: \_\_\_\_\_

