DATE 23 Dece	ember 1964 of 10	TMC SPECIFICATION NO. S-890	0
PKC TKA COMPILED	CHECKED	TITLE:	
02	OVED KA	Typed by mtp	

TEST PROCEDURE

for

VLFC-1 (RAK-43) - VLF FREQUENCY SYSTEM

TMC SPECIFICATION NO. S-890

TKA
COMPILED CHECKED

TITLE: TEST PROCEDURE FOR VLFC-1 (RAK 43) - VLF FREQUENCY SYSTEM

Typed by mtp

TABLE OF CONTENTS

ITEM	SECTION	PAGE
Introduction		3
Equipment Required	I	4
Preliminary Checkout	11	4
Procedure	III	4-8
Test Data Sheet		9 & 10

TMC SPECIFICATION NO. S-890

TMC SPECIFICATION NO. S-890

TITLE: TEST PROCEDURE FOR VLFC-1 (RAK-43) - VLF FREQUENCY SYSTEM

Typed by mtp

INTRODUCTION

The TMC VLFC-1 is a precision, Very Low Frequency Comparison System for the reception of standard frequency stations in the VLF range for direct comparison with local standards. This consists of the following units:

LFSA-1	Synthesizer
VLRA-1	VLF Receiver
PFCB-1	Frequency Standard
CSS-2	Frequency Standard
BPSD-1	Battery Supply

In the RAK-43 configuration, an LSP-4 monitor speaker, and an HPP-1 power distribution panel are also provided.

The units in this system are in the standard 19" rack mounted configuration. Almost all of the circuitry is in the form of plug-in printed circuit boards.

This specification covers the operational check of the overall system. A separate specification covers the testing of each individual unit in the system.

DATE 23 December 1964 SHEET 4 OF 10		TMC SPECIFICATION NO. 5-890	0
PLATKA COMPILED	CHECKED	TITLE: TEST PROCEDURE FOR VLFC-1 (RAK-43) - VLF FREQUENCY STANDARD	
APPROVED		Typed by mtp	

I. EQUIPMENT REQUIRED

- 1. Ultra-stable standard (1 mc).
- 2. VLF Signal Generator.
- 3. VLF Antenna Installation.
- 4. VOM Simpson #260 or equivalent.
- 5. Ballantine RMS Voltmeter, or equivalent.
- 6. Dummy Load D 100-4.

II. PRELIMINARY CHECKOUT

1. Mechanical Check

a. Defective panels, proper action of slides, etc.

2. Check inter-connecting cables

- a. Proper hook-up per cable diagram.
- b. Proper routing; freedom from snags.

III. PRELIMINARY OPERATIONS

1. Set controls as follows:

MODULAR UNIT	SWITCH OR CONTROL	POSITION
VLRA	POWER BATTERY AF GAIN	ON (Upper) IN Fully Counter- clockwise
	AGC DECAY CHAN. SEL.	MAN RF Selected Receiver Channel
	NOISE SILENCER BFO Control RF GAIN LINE LEVEL AF-RF	OFF Mid-position Mid-position Mid-position RF
LFSA	POWER 10 KC, 1KC, .1KC 10 CPS, and 1 CPS	On (Upper) At selected frequency of VLRA receiver,
		<pre>(observe nixie lamps for proper readout.)</pre>

III. PRELIMINARY OPERATIONS - Cont'd

MODULAR UNIT	SWITCH OR CONTROL	POSITION
CSS	AMPLIFIERS *BAT. SYNCHRONIZE METER FUNCTION FINE FREQ ADJUST	STANDBY IN OFF 24V At initial setting
PFCB	ON-OFF *BAT MULTIPLIER METER SCALE	on in 6 parts in 10 ⁿ off
BPS	METER SWITCH	BATTERY GROUP - 1 CONDITION

*The battery switches are placed in the OUT position only when Battery Power Supply BPS is not supplied with batteries.

IV. SYSTEM TEST PROCEDURE

Individual units in the system should be in good working order as per their individual test specification, as this procedure will cover a system check only.

- Steps (1) through (10) are performed during a 24-hour warm-up period. This is necessary to insure a stable 1 mc frequency output of Frequency Standard CSS. Also, the procedures that follow assume that at least two batteries (one for each battery group) are supplied with the Battery Power Supply BPS.
- 1. On Very Low Frequency Receiver VLRA, Frequency Standard CSS, Precision Frequency Comparator PFC and Low Frequency Synthesizer LFSA, observe that POWER lamps are lit.
- 2. On Power Panel HPP, connect ACVM to each utility outlet. ACVM should indicate 115 VAC (or 230 VAC if used).
- 3. On Frequency Standard CSS, observe function. Meter should indicate approximately 24 volts.
- 4. On Battery Power Supply BPS, observe that meter indicates within BAT-TERY CONDITION area. Set METER SWITCH at BATTERY GROUP-2 CONDITION and observe that meter indicates within BATTERY CONDITION area. Meter should indicate between 500 and 600 milliamperes. Then, set METER SWITCH at BATTERY GROUP-1 CHARGE. Meter should indicate between 0 and 100 milliamperes.

DATE 23 December 1964

SHEET 6 OF 10

OMPILED

TMC SPECIFICATION NO. S-890

0

CHECKED

TEST PROCEDURE FOR

VLFC-1 (RAK-43) - VLF FREQUENCY STANDARD SYSTEM

APPROVED

Typed by mtp

IV. SYSTEM TEST PROCEDURE - Cont'd

- 5. Disconnecta-c line power from VLFC system.
- 6. On Very Low Frequency Receiver VLRA, Frequency Standard CSS, Precision Frequency Comparator PFCB, and Low Frequency LFSA, observe that POWER lamps go off and BATTERY lamps light when battery is supplied.
- 7. On Frequency Standard CSS, function meter should indicate approximately 24 volts. Set METER FUNCTION selector switch at OVEN TEMP.
- 8. Re-connect a-c line power to VLFC system and observe that BATTERY lamps and POWER lamps referred to in Step (6) above go off and on.
- 9. On Battery Power Supply BPS, set METER SWITCH at BATTERY GROUP-1 CONDITION. Meter should indicate between 500 and 600 milliamperes. Then, set METER SWITCH at BATTERY GROUP-2 CHARGE. Meter should indicate between 0 and 100 milliamperes. Set METER SWITCH at BATTERY GROUP-1 CONDITION.
 - 10. On Very Low Frequency Receiver VLRA, perform the following:

NOTE: During system checkout, the VLRA receiver should be tuned to a strong VLF station that is transmitting at a known frequency stability of 1 part in 1011.

- **8.** Turn RF GAIN control in clockwise and then counter-clockwise diretion, observing corresponding changes on meter. Set RF GAIN control at mid-position.
- b. Set AF-RF switch at AF. Turn LINE LEVEL control in clockwise then counter-clockwise direction, observing corresponding changes on meter. Set RF GAIN control at mid-position and set AF-RF switch at RF.
 - c. Adjust AF GAIN control for comfortable audio level.
 - d. Adjust BFO control as required for desired tone.
- e. Set AGC DECAY switch at best position suitable for speed of transmission.
- f. If necessary, adjust NOISE SILENCER control to reduce noise present in received signal, observe action on weak channel with an oscilloscope across 600 ohm line, and center tap on VLRA-1.
- g. Check remaining frequency channels by using CHAN SEL switch, and repeating Steps (c) through (f). Then reset CHAN. SEL. switch to desired frequency.
- h. Connect headset with an impedance of 600 ohms to PHONE jack, and listen for audio. Then, disconnect headset from PHONE jack.
 - 11. Allow Frequency Standard CSS to warm up for a 24-hour period.

DATE 23 December 1964

SHEET 7 OF 10

4_TKA

MPILED

TMC SPECIFICATION NO. S-890

0

CHECKED

TITLE: TEST PROCEDURE FOR VLFC-1 (RAK-43) - VLF FREQUENCY STANDARD SYSTEM

APPROVED

Typed by mtp

IV. SYSTEM TEST PROCEDURE - Cont'd

- 12. On Frequency Standard CSS, perform the following:
 - a. Observe that meter indicates within the green area.
- b. Set METER FUNCTION switch at 24V. Observe that meter indicates approximately 24 volts.
- c. Sequentially set METER FUNCTION selector switch at 100 KC, 1 MC and 10 MC while observing function meter. Meter should indicate at least 1 volt rms for each switch position.
 - d. Set METER FUNCTION switch at OVEN TEMP.
- 13. On Low Frequency Synthesizer LFSA, observe SYN ALARM lamp and SYNCHRO-NIZE meter for one of following conditions:
- a. SYN ALARM lamp is off and pointer on SYNCHRONIZE meter is centered within green area.
- b. SYN ALARM lamp is off and pointer on SYNCHRONIZE meter is in yellow or red area (left or right of green center area.)
- c. SYN ALARM lamp is flickering on and off intermittently, and pointer on SYNCHRONIZE meter is in yellow or red area (left or right of center green area.)
 - NOTE: The direction of rotation for the FINE FREQ ADJUST control (-Af or +Af is determined by which color area (right or left of green) the pointer on the Low Frequency Synthesizer SYNCHRONIZE meter lies. If the meter pointer is in the red-yellow area to the right or left of the green (center) area, adjust the FINE FREQ ADJUST control in a clockwise or counter-clockwise direction, respectively.
- 14. Repeat Step (13) and NOTE above as many times as necessary until pointer on SYNCHRONIZE meter of Low Frequency Synthesizer LFSA centers in green area.
- 15. On Frequency Standard CSS, set SYNCHRONIZE switch at ON.

 Observe SYNCHRONIZE meter. If meter is centered in green area, proceed to Step (16). If not, Repeat Steps (13), (14) and NOTE above.
 - 16. On Precision Frequency Comparator PFCB, perform the following:
 - a. Connect coaxial jumper between front panel REF IN and TEST IN jacks.
- b. Set METER SCALE switch at OFF and observe initial movement of recorder chart and pen. The pen markings as indicated on recorder chart should be

TMC SPECIFICATION NO. S. 890

TKA
COMPILED CHECKED TITLE: TEST PROCEDURE FOR
VLFC-1 (RAK-43) - VLF FREQUENCY STANDARD SYSTEM

Typed by mtp

APPROVED

IV. SYSTEM TEST PROCEDURE - Cont'd

centered at zero. If not, remove snapbutton cover centrally located at the bottom of recorder, and adjust screwdriver control on recorder for zero indication on recorder chart.

- c. Set Scale Multiplier to 6 parts in 10^m and successively set Meter Scale switch at 5, 2 and 1, and observe markings on recorder chart for zero indication at each switch position. Remove top cover on PFCB-1 and adjust R610 on card Z601 for zero if necessary.
- d. Set Multiplier switch on 7, 8, 9 and 10 parts in $10^{\rm m}$, and observe markings on recorder.
- e. Replace covers on recorder, and disconnect coaxial jumper connected between REF IN and TEST IN jacks.
- 17. Connect the ultra-stable standard signal (1MC 600 MV or more) to the test input (J102) of the PFCB-1, and observe over a period of time the drifts and variations on the various scale settings and the multiplier setting of the PFCB-1 recorder.

NOTE: During the hours of sunrise and sunset, the rate of DIURNAL drift may exceed the tracking rate of VLFC-1 system adjustment, and calibration should not be attempted at these times.

- 18. Connect VLF generator to antenna input of VLRA and RMS Voltmeter to 600 audio line, and check signal-to-noise ratios for 0.1 uv at 15 db using DL 100-4 for noise reference.
- 19. Check channels for AGC dynamic range 80 db for less than 3 db line variation, 1 uv to 10 mv.
- 20. Switch to Manual RF Gain and check sideband rejection of 60 db or greater, (RF Gain maximum).
 - 21. Check chart stability 109 for 24 hrs.
 - 22. Check chart stability $\pm 2 \times 10^{10}$ for five minutes.
 - 23. Check chart stability coincidence 10 seconds for 10⁸.

TE 23 De	of 10	TMC SPECIFICATION NO. 5-890
KU TKA	CHECKED	TITLE: TEST PROCEDURE FOR VLFC-1 (RAK-43) - VLF FREQUENCY STANDARD SYSTEM
APPR	OVED	Typed by mtp
	•	THE TECHNICAL MATERIEL CORP. MAMARONECK, N.Y.
		TEST DATA SHEET
		<u>for</u>
		VLFC-1 SYSTEM (RAK-43)
SER	IAL NO.:	
MFG	. NO.:	
	POWER ON:	OK
		OK
		ER LINE: OK
	BATTERY CON	DITION 1: OK 2: OK
	VLRA:	ок
	CSS:	OK
	LFSA:	OK
	PFCB:	OK
	EXTERNAL ST	ANDARD CHECK: OK
DATE:		
TESTER:		

29 December	1964	SPECIFICATION	NO Sono
0	10 I MC	SPECIFICATION	NO. 3.890
TKA		T PROCEDURE FOR C-1 (RAK-43) - VLF FREQUEN	NCY STANDARD SYSTEM
APPROVED	Typed by	mtp	
		TEST DATA SHEET	
		for	
	VLR	A-1 SYSTEM - VLFC-1	A.
	FREQUENCY	SENSITIVITY	AGC
Channel	кс	0.1 uv for 15 db S+N	
1 2			
3 4			timocratia de ratio
5 6			of Hardes
7 8			
9 10			
SIDERAND RE	JECTION GREATER T	HAN 60 DB	DK.
	JAVIION GIMILLIN I	man oo bb	71.
	СН	ART READOUT PFCB-1	
Stability:	1 part 10 ⁹ 24 h	rs. OK	
	<u>+</u> 2 parts 10 ¹⁰	5 min. OK	
	10 ⁸ for 10 seco (2 readouts)	nds OK	
DATE:			

REVISION SHEET			THE TECHNICAL MATERIEL CORP. MAMARONECK NEW YORK	S-890 LIST NO.	0	
DATE REV. SHEET EMN #			EMN #			
12/30/		1 of		O= ORIGINAL RELEASE FOR PROD		APP.
						<u> </u>
	<u>-</u>					<u> </u>
		 				<u> </u>
		<u> </u>				
						ļ
				• · · · · · · · · · · · · · · · · · · ·		
		<u> </u>				
	 	<u> </u>				
		ļ				
						,
		1	1			
		<u> </u>			······	
		<u> </u>			<u> </u>	
				<u> </u>		
						
						ļ
		-				ļ
						
 		1				
		ļ				
1		1				İ